

3	Supplying and fixing skin Galvalume corrugated colour steel sheet in Roof with necessary over laps as per manufacture's recommendation, using 0.5mm TCT 550 Mpa profiled steel passivated and clear resin coated (aluminium zinc alloy coating) sheets and fixing accessories such as self drilling self tapping fastener acrylic sealants profiled loom, neoprene fillers etc., including cost of all materials labour wastage tools, tackles, equipment transportation etc., complete all as specified and directed by the Engineer-in-charge. Note : 1) The work involves working at a height of 15M (approx.). Hence, the quoted rate shall deem to include the cost of the same. 2) Necessary safety permits to be obtained from safety department before commencement of work on day to day	1800	M2
---	--	------	----